BRUHAT BANGALORE MAHANAGARA PALIKE

BILL OF QUANTITIES (BOQ)

Name of the Work: Improvements drains and Covering Slabs in ward no 05.Jakkur

Sl. No.	Approved Qty.	Description	Unit	Issued to Technical Manager , KRIDL	
				In Figures	In Words
1	777.85	Earth work excavation for foundation of building water supply sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width in Ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications	Cum	86.92	Rupees Eighty Six and Ninety Two Paise Only
2	2624.40	Removing B.S.Slab of drain and stacking (P-25, It;5.32)	Sqm	65.72	Rupees Sixty Five and Seventy Two Paise Only
3	2624.40	Refixing stone.Slab of drain and pointing in CM(1:3) (P-25, It;5.33)	Sqm	80.56	Rupees Eighty and Fifty Six Paise Only
4	874.80	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete 7.5 cms thick (P-12, It.4.3)	Sqm	665.68	Rupees Six Hundred Sixty Five and Sixty Eight Paise Only
5	157.68	KSRB 4-1.3:Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation and plinth including cost of all materials, labour, HOM of machienry, curing complete as per specifications. Specification No.KBS 4.1, 4.2 (P-12, It.4.3)	Cum	5159.02	Rupees Five Thousand One Hundred Fifty Nine and Two Paise Only
6	2208.00	KSRB 5-14:Providing and constructing load bearing wall with solid concrete blocks having block density not less than 1800kg/m3 having a minimum average compressive strength 5.0 N/mm2 confirming to IS:2185(part);2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour charges, scaffolding, curing, hire charges of machineries etc. complete as per specifications.KBS No.5.4 with solid concrete block of size 400x200x200 mm (P-25, It.5.27.1)	Sqm	993.22	Rupees Nine Hundred Ninety Three and Twenty Two Paise Only
7	131.40	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 Kgs, with 20mm and down size graded granite metal coarse aggregtes @ 0.69cum and line aggregates @ 0.459 cum,machine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No.KBS 4.1, 4.2 (P-12, It.4.6)	Cum	5767.46	Rupees Five Thousand Seven Hundred Sixty Seven and Forty Six Paise Only
8	2365.20	Providing and fixing 10 cm thick pre cast reinforced concrete slab as per design and drawing material cost, transportation, hire charges of machinery complete with all lead and lift conveyance charges labour charges inclusive of cost of all materials	Sqm	1777.75	Rupees One Thousand Seven Hundred Seventy Seven and Seventy Five Paise Only

Signature of the contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

19/04

Executive Engineer

19/04

Sl. No.	Approved Qty.	Description	Unit	Issued to Technical Manager , KRIDL	
				In Figures	In Words
9	777.85	Conveying the excavated earth (lead charges) to a with lead of 10kms with all lead and lift. including loading and unloading charges etc., complete as per direction of Engineer in charge	Cum	106.00	Rupees One Hundred Six Only

1. The work should be executed as per the specification and standard specified by the PWD & Other specifications of the Bangalore Mahanagara Palike and as directed.
2. The work should be carried out as per the directions and instructions of the concerned Engineer
3. The Contractor should maintain the quality of work as per the standard specifications.

19/04

Executive Engineer (Byatarayanapura)
Bruhath Bangalore Mahanagara Palike

I am prepared to take up the above work at the rates quoted by me in the Schedule 'B' 19/04

CONTRACTOR

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010